

06 22 MILLWORK

Part 1 General

1.1 Documents

- .1 The Agreement and the General Conditions shall govern all trades under these specifications and shall be considered part of and are to be read in conjunction with this Section.

1.2 Scope

- .1 Supply and install upper and lower cabinets in the New EarlyON Kitchen.
- .2 Supply and install Plastic Laminate countertops for all lower cabinets.
- .3 Supply install all cabinetry hardware as required.
- .4 Supply and install Plastic Laminate countertops in New EarlyON Kitchen, as shown on the drawings.

1.3 Shop Drawings

- .1 Submit shop drawings for review by consultant.

Part 2 Products

2.1 Seasoning

- .1 All finish lumber shall be well seasoned and kiln-dried to a maximum moisture content range for exterior work of 9 to 12%, for interior work - 6 to 8%.
- .2 Plywood to be good both sides for open shelf construction. Baltic Birch plywood for exposed wood finish.

2.2 Plastic Laminate

- .1 Plastic laminate shall be Wilsonart Graphite Nebula 4623-60 or equal approved alternative.

2.3 Cabinet Hardware

- .1 For all cabinet doors and drawers provide all necessary matching hinges, pulls, slides and catches. Provide bar type hand pulls of simple contemporary design with 30 mm minimum distance between handle and door or drawer. Do not use knob type pulls. Where bar type

pulls are used these must have rounded corners to Consultant's approval. Grade of hardware to be of medium quality.

2.4 Samples

- .1 Submit samples of typical cabinet unit showing construction of styles, shelving, doors, hinges, pulls, drawer glides, and catches for approval.

2.5 Cabinets

- .1 Cabinets to be pre-assembled boxed units with Summit style, Maple doors and drawers as manufactured by Kitchen Craft.
- .2 Cabinets to be equipped with soft-close hardware.

Part 3 Execution

3.1 Workmanship

- .1 All cabinet work shall be of the best grade of materials and workmanship of their respective kinds, and shall incorporate skilled workmanship and modern machinery to provide work equal to the standards of recognized suppliers of furniture and cabinet work.
- .2 All unfinished millwork to receive finish as per painting section.

3.2 Examination of Other Trades

- .1 This Contractor, before commencing work shall carefully examine the work of other trades, and if any condition exists that will adversely affect the work of this contract in any way, he shall report it to the Consultant in writing. Commencement of work by this Contractor shall signify his acceptance of the work of other trades.

3.3 Delivery and Protection

- .1 Millwork shall not be delivered before it is required.
- .2 Work shall not be delivered to the building before structure is sufficiently dry and ready to receive finished millwork.
- .3 Confer with Contractor as to a designated place in the premises for receiving of millwork.

3.4 Field Dimensions

- .1 Take field dimensions and fabricate work to suit dimensions.

3.5 Cutouts

- .1 All cutouts in plastic laminate covered counters shall be made with radius corners, and all units shall be free of cracked, chipped and damaged plastic. Where joints occur in plastic covered units, they shall be blind splined to provide a tight hairline joint.

3.6 Cabinet Construction

- .1 All cupboards, cabinets, open shelving, etc., shall be assembled complete in such sections as may be readily brought into the building, together with all loose parts of the assembly which are to be installed during construction.
- .2 Cupboards, counters, etc., shall be built as complete rigid units.

END OF SECTION